

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23161-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 32-7S-21W
1820 feet from S Section Line, 100 feet from W Section Line
Lease Name: TYNER STEHNO Well #: 1-32
County: GRAHAM Total Vertical Depth: 3695 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	221		

\$1 120.09

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/02/2006 12:00 PM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.
No arbuckle found.

Plugging Proposal Received By: HERB DEINES Witness Type: NONE
Date/Time Plugging Completed: 04/02/2006 3:15 PM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 1775' w/25 sxs.
2nd. Plug at 875' w/100 sxs.
3rd. Plug at 275' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

Remarks: SWIFT SERVICES, INC.

Plugged through: DP

INVOICED
DATE 4-7-06
NO. 2006061445

District: 04

Signed _____

(TECHNICIAN)

RECEIVED

APR 07 2006

KCC WICHITA

Form CP-2/3

APR 05 2006

PCT