

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-03768-00-00  
Spot: NENESW Sec/Twnshp/Rge: 4-17S-11W  
2310 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: RIEMANN J Well #: 5  
County: BARTON Total Vertical Depth: 3311 feet

Operator License No.: 9067  
Op Name: DAMAR RESOURCES, INC.  
Address: PO BOX 70 234 W. 11TH, STE A  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3299	0	150 SX
SURF	10.75	279	0	150 SX

\$ 107.61

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/30/2006 9:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: CURTIS R. LONGPINE Company: DAMAR RESOURCES, INC. Phone: (785) 625-0020

Proposed  
Plugging  
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/30/2006 12:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perforated at 1450' and 740'.  
Ran tubing to 2000'.  
Pumped 100 sxs 60/40 pozmix - 10% gel cement with 300# hulls.  
Pulled to 1000'.  
Circulated with 90 sxs cement with 200# hulls.  
POOH. Tied onto casing and pumped 60 sxs cement.  
Max. P.S.I. 250#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
2931	3195		

INVOICED

4-7-06

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

RATE 4-7-06  
TEL. NO. 20060614416

District: 04

*DM*

Signed \_\_\_\_\_

*Case Morris*

(TECHNICIAN)

RECEIVED

APR 07 2006

KCC WICHITA

Form CP-2/3

APR 05 2006

*PKT*