

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-20886-00-00  
Spot: NWNESE Sec/Twnshp/Rge: 31-18S-11W  
2475 feet from S Section Line, 495 feet from E Section Line  
Lease Name: KIMPLER B Well #: 4  
County: BARTON Total Vertical Depth: 3416 feet

Operator License No.: 31561  
Op Name: HOFFMAN, CHRIS DBA C & K OIL COM  
Address: 410 B STREET PO BOX 531  
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3405	0	125 SX CMT
SURF	8.625	254	0	225 SX CMT

\$ 111.02

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/04/2006 8:00 AM  
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.  
Proposal Rcvd. from: CHRIS HOFFMAN Company: C&K OIL COMPANY Phone: (620) 786-0644

Proposed Plugging Method: Ordered 280 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Tubing stuck in the hole at 2325'. Fluids 300'.  
Gressel Oil Field Service - shot a two hole perf at 1050' - 660' - 300'.  
RIH with tubing - circulated 40 bbls water to circulate oil out of the hole to get perforation gun down hole.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/04/2006 3:40 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Classic Well Service RIH with tubing to 2000'.  
Copeland rigged to tubing and pumped 25 sxs neat followed with 75 sxs 60/40 pozmix with 200# hulls mixed in.  
Pulled tubing to 1000'. Copeland rigged to tubing and pumped 135 sxs cement with 300# hulls mixed in cement - did not circulate.  
Pulled tubing to 500' and pumped 15 sxs to circulate cement into pit.  
Pulled tubing - Copeland rigged to 4 1/2" casing with a swedge and pumped 25 sxs cement. Max. P.S.I. 300#. S.I.P. 200#.  
Tied onto 8 5/8" casing and pumped 5 sxs cement. Max. P.S.I. 200#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3405	3416	OH	Completed

Remarks: GRESSEL OIL FIELD SERVICES, INC.-TICKET#030308.

Plugged through: TBG

District: 04

Signed

(TECHNICIAN)

RECEIVED

APR 07 2006

KCC WICHITA

Form CP-2/3

APR 05 2006


PET

AL TIPTON #B-4 KIMPLER 31-18-11W  
 200'NW, NE NE SE

P.O. BOX 157, HAYS, KS.  
 CONTR DUKE DRIG. CO. CTY BARTON

GEOL VIC REISERER FIELD KIMPLER

E 1826 KB CM 3/15/75 CARD ISSUED 4/24/75 IP P 53 BOPD + TR WTR  
 ARB 3405-3410



API 15-009-20,886

SMP	TOPS	DEPTH	DATUM
HEEB		2988	-1162
BR LM		3100	-1274
KC		3112	-1286
ARB		3399	-1573
TD		3410	-1584
DD TD		3416	-1590

8-5/8" 254/225sx, 4 1/2" 3405

NO LOG

DST (1) 3402-10/45-45-45-45, REC 120'  
 GIP, 500'OIL + SMALL AMT M, SIP  
 964-907#, FP 122-205#

MICT - CO TD 3410, A. 400, SWB 2.32  
 BOPH, FU 1300'OIL/4HRS, SWB 3.48BOPH,  
 DD 3413, SWB 2.32BOPH, A 600, DD 3416,  
 CO & POP

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS