

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-085-20070-00-00
Spot: NESWSWNW Sec/Twnshp/Rge: 14-5S-15E
3181 feet from S Section Line, 4793 feet from E Section Line
Lease Name: ATWATER FARMS Well #: 5-14
County: JACKSON Total Vertical Depth: 2383 feet

Operator License No.: 33233
Op Name: HEARTLAND OIL & GAS, INC.
Address: 1610 INDUSTRIAL PARK DRIVE
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2358		180 SX CMT
SURF	8.625	235		120 SX CMT

77.45

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/31/2006 8:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 2313' TO 2212', CMT FROM 2212' TO 1928', GEL FROM 1928' TO 250', CMT FROM 250' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: PARTIAL
Date/Time Plugging Completed: 01/31/2006 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

TAGGED BOTTOM AT 2192'. PUMPED 35 SACKS OF CEMENT AND 1 SACK OF COTTON SEED HULLS FROM 2192' TO 1886'. HAD 8 SACKS OF GEL FROM 1886' TO 300'. PUMPED 40 SACKS OF CEMENT FROM 300' TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2160	2162		
2154	2156		
2099	2101		
2073	2075		
2054	2056		
2030	2032		
2026	2027		
2018	2020		
1978	1980		

RECEIVED
KCC DISTRICT #3
APR 4 2006 TCH
CHANUTE, KS

RECEIVED
APR 10 2006
KCC WICHITA
INVOICED

Remarks:

Plugged through: TBG

4-10-06
2006061461

District: 03

Signed Taylor C. Herman
(TECHNICIAN)

PKT