

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-125-27582-00-00  
Spot: NENWNW Sec/Twnshp/Rge: 27-33S-14E  
4640 feet from S Section Line, 4180 feet from E Section Line  
Lease Name: EDDS Well #: 22  
County: MONTGOMERY Total Vertical Depth: 750 feet

Operator License No.: 33074  
Op Name: DART CHEROKEE BASIN OPERATING  
Address: 600 DART RD PO BOX 177  
MASON, MI 48854

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	750	0	
SURF	7	20	0	

\$ 35.00

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/23/2005 8:00 AM  
Plug Co. License No.: 30670 Plug Co. Name: KEPLEY WELL SERVICE, A GENERAL PARTNERSHIP  
Proposal Rcvd. from: TONY WILLIAMS Company: DART CHEROKEE BASIN OPERATI Phone: (620) 331-7870

Proposed Plugging Method: Run 1 inch cement string inside and outside the 2.875 inch pipe to TD. Cement well from bottom to top.

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE  
Date/Time Plugging Completed: 12/23/2005 5:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

575 ft of 1 inch pipe was washed down the inside of 2.875 inch casing. 400 ft of 1 inch pipe washed down the annular space between the 2.875 inch casing and the surface pipe. The well was filled from bottom to top thru these 1 inch strings of pipe. The 1 inch pipe was removed and then additional cement added to bring cement to the top of well. The well was cut off below plow depth and the location restored. Altogether, 140 sacks of portland cement were used to plug well.

Perfs:

RECEIVED  
KCC DISTRICT #3

APR 6 2006 AMD

CHANUTE, KS

INVOICED

DATE: 4-10-06  
2006041458

Remarks:

Plugged through: CSG

District: 03

Signed

Alan M. Dunning

(TECHNICIAN)

RECEIVED  
APR 10 2006  
KCC WICHITA

Form CP-2/3

PKT