

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-125-27598-00-00

Spot: SESWNW

Sec/Twnshp/Rge: 27-33S-14E

2860 feet from S Section Line, 4180 feet from E Section Line

Lease Name: EDDS

Well #: 27

County: MONTGOMERY

Total Vertical Depth: 750 feet

Operator License No.: 33074

Op Name: DART CHEROKEE BASIN OPERATING

Address: 600 DART RD PO BOX 177
MASON, MI 48854

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	750	0	
SURF	7	20	0	

\$ 35.00

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/21/2005 8:00 AM

Plug Co. License No.: 30670

Plug Co. Name: KEPLEY WELL SERVICE, A GENERAL PARTNERSHIP

Proposal Rcvd. from: TONY WILLIAMS

Company: DART CHEROKEE BASIN OPERATI Phone: (620) 331-7870

Proposed
Plugging
Method:

Plug well by connecting to wellhead and squeezing cement into well. When full of cement, shut the well in with pressure.

Plugging Proposal Received By: ALAN DUNNING

WitnessType: NONE

Date/Time Plugging Completed: 12/21/2005 5:00 PM

KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

A 1 inch cement string was washed down the 2.875 inch casing to 725 ft. The well was filled from bottom to top thru the 1 inch cement string. The 1 inch cement string was removed and then additional cement added to bring cement to the top of well. Altogether, 49 sacks of portland cement were used to plug the well. The well was cut off below plow depth and the location restored.

RECEIVED
KCC DISTRICT #3

APR 6 2006 AMD

CHANUTE, KS

INVOICED

4-10-06

2006061458

Remarks:

Plugged through: CSG

District: 03

Signed

Alan Dunning
(TECHNICIAN)

RECEIVED
APR 10 2006
KCC WICHITA

Form CP-2/3

PRT