

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-085-20075-00-00
Spot: SENWSWNE Sec/Twnshp/Rge: 15-5S-15E
3420 feet from S Section Line, 2130 feet from E Section Line
Lease Name: ATWATER Well #: 7-15
County: JACKSON Total Vertical Depth: 2404 feet

Operator License No.: 33233
Op Name: HEARTLAND OIL & GAS, INC.
Address: 1610 INDUSTRIAL PARK DRIVE
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2376		190 SX CMT
SURF	8.625	243		120 SX CMT

78.13

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/26/2006 8:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 2327- TO 2236' CMT FROM 2236' TO 1942', GEL FROM 1942' TO 250', CMT FROM 250' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN Witness Type: PARTIAL
Date/Time Plugging Completed: 01/31/2006 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

TAGGED BOTTOM AT 2183'. PUMPED 35 SACKS OF CEMENT AND 1 SACK OF COTTON SEED HULLS FROM 2183' TO 1877'. PUMPED 9 SACKS OF GEL FROM 1887' TO 300'. PUMPED 30 SACKS OF CEMENT FROM 300' TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2184	2186		
2177	2179		
2150	2151		
2123	2125		
2097	2099		
2076	2078		
2049	2051		
2038	2040		
1992	1994		

RECEIVED
KCC DISTRICT #3
APR 4 2006
CHANUTE, KS
TCH

RECEIVED
APR 10 2006
KCC WICHITA
INVOICED

Remarks:
Plugged through: TBG

4-10-06
2006061461

District: 03

Signed Taylor C. Herman
(TECHNICIAN)

PKT