

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-085-20063-00-00  
Spot: NENE Sec/Twnshp/Rge: 30-6S-16E  
4594 feet from S Section Line, 510 feet from E Section Line  
Lease Name: AMON Well #: 41-30  
County: JACKSON Total Vertical Depth: 2222 feet

Operator License No.: 33233  
Op Name: HEARTLAND OIL & GAS, INC.  
Address: 1610 INDUSTRIAL PARK DRIVE  
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2210		466 SX CMT
SURF	8.625	217		80 SX CMT
T1	2.875	865		

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/02/2006 8:00 AM  
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.  
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 2165' TO 2134', CMT FROM 2134' TO 1586', GEL FROM 1586' TO 250', CMT FROM 250' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN Witness Type: PARTIAL  
Date/Time Plugging Completed: 02/02/2006 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

TAGGED BOTTOM AT 2150'. PUMPED 85 SACKS OF GEL AND 65 SACKS OF CEMENT PLUS 1 SACK OF COTTON SEED HULLS. CEMENT FROM 2150' TO 1881' AND GEL FROM 1881' TO 251'. PUMPED 30 SACKS OF CEMENT FROM 251' TO SURFACE.

RECEIVED  
KCC DISTRICT #3

APR 4 2006 TCH

CHANUTE, KS

Perfs:

Top	Bot	Thru	Comments
2082	2084		
2042	2045		
1987	1990		
1962	1964		
1953	1955		
1947	1950		
1921	1924		
1866	1868		
1762	1764		
1730	1732		
1636	1638		

RECEIVED  
APR 10 2006

KCC WICHITA

INVOICED

Remarks:

Plugged through: TBG

District: 03

Signed

Taylor C. Herman  
(TECHNICIAN)

(TECHNICIAN)

PKY