

6 030772

269 R

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-21, 249-00-00

NENESW SEC. 36, T 7 S, R 24 W

2310 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Lease Name KEITH Well # 1

Operator: A. L. ABERCROMBIE INC.

County GRAHAM 126.43

Name & Address BOI UNION CENTER

Well Total Depth 3890 feet

WICHITA, KANSAS

Conductor Pipe: Size feet

67202

Surface Casing: Size 8 5/8 feet 245'

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor ALLIED CMT. CO. License Number

Address PLAINVILLE, KANSAS

Company to plug at: Hour: 9:15 AM Day: 25 Month: 7 Year: 19 86

Plugging proposal received from BILL SOWLES

(company name) A. L. ABERCROMBIE (phone)

were: 8 5/8" SET @ 245' w/185SX. 4 1/2" SET @ 3889' w/150SX. PBD 3843'

PERFS. 3815-18' NO PIPE PULLED ORDER 200SX. ATL CMT. MIX.

5SX. HULLS ALLIED CMT. CO. COMPANY WATER TRUCKS

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 9:15 AM Day: 25 Month: 7 Year: 19 86

ACTUAL PLUGGING REPORT TIE ON TO 4 1/2" CASING. MIX. & Pump 3SX. HULLS 115SX. ATL CMT. MIX MAX. PSI 1500# CLOSE IN 400#

TIE ON TO BACK SIDE MIX. & Pump 2SX. HULLS 110SX. ATL CMT. MIX. MAX. PSI 500# CLOSE IN 150# PLUG COMPLETE.

RECEIVED

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

I (did / did not) observe this plugging.

DATE AUG 6 1986

AUG 4, 1986

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 14635

7-25