

6010187

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-22039-00-00
SE, SEC. 36, T. 7 S, R. 24 W
2440 feet from N 1/2 section line
1520 feet from W 1/2 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9514
Operator: D. & D. oil co.
Name & Address: Box 321
Pratt Ks.

Lease Name Ray Well # A-1
County Graham
Well Total Depth 3880 126.10 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 199

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well (D&A)

Other well as hereinafter indicated _____ # 5149

Plugging Contractor Wheat States Oil Field Inc. License Number 1800 362-0945
Address Box 329 Pratt Ks.

Company to plug at: Hour: AM Day: 15 Month: 8 Year: 19 84

Plugging proposal received from Steve Fellers
(company name) Wheat States (phone) 1800 362-0945

were: order 185 sx. cement 50/50 pormix 6% Gel. 3% o.c.c.
1. 5x. hulls 1. 8 5/8 plug 1. 5x Flow Seal.

Heavy mud between all plugs.
Pump cement down drip pipe.

Elev. 2356 Anhydrite 1876-1912. Arbuckle. No. Dakota. 1450
Plugging Proposal Received by Del F. Belthazor (TECHNICIAN)
906 = 1200

Plugging Operations attended by Agent?: All _____ (Part) _____ None _____

Operations Completed: Hour: 8 AM Day: 15 Month: 8 Year: 19 84

ACTUAL PLUGGING REPORT circulated @ 1900 for. 20 mi
25 sx @ 1900

100 5x @ 1200 mixed with 15x Flow seal.
40 5x @ 210 dumped 15x. hulls pushed plug to 40'
10 5x @ 40
10 5x in Rat Hole.

Remarks: Cementing Co. Allied
(If additional description is necessary, use BACK of this form.)

I (did) did not) observe this plugging operation.

check ed. DATE 8-28-84 Signed Del F. Belthazor (TECHNICIAN)
AUG 27 1984
INV. NO. 3422 AUG 27, 1984
8-15 CONSERVATION DIVISION Wichita, Kansas
FORM CP-2/3 Rev. 01-84