

9-26

68
R

6-100441

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-22,649 -00-00

SE SE NE /4 SEC. 04, 07 S, 23 W
3040 feet from S section line
400 feet from E section line

Operator license# 05058

Lease Trexler well # 1

Operator: Griggs Oil, Inc.

County Graham

126.42

Address: 107 North Market
Suite 800
Wichita, Kansas 67202

Well total depth 3890 feet
Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 212 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Abercrombie RTD License# 05422

Address: Wichita, Kansas 67202

Company to plug at: Hour: ?? Day: Month: Year:

Plugging proposal received from: Harold Maley

Company: Abercrombie RTD phone:

Were: **Spot plugs through drill pipe w/ heavy mud between all plugs.**

1st plug @ 2050 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1280 feet " 100 " Mousehole: sacks

3rd plug @ 260 feet " 40 "

4th plug @ 40 feet " wiper plug & 10 sx

RECEIVED
STATE CORPORATION COMMISSION

NOV 12 1991 11-12-91

Plugging Proposal Received by: David K. Wann

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 9:00 pm, Day: 26, Month: September, Year: 1991

Actual plugging report: Hole reported plugged as above.

Order 190 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 2381 GL, Anhydrite depth: 2047 - 2080 feet

Did NOT penetrate Arbuckle, cemented by Allied

I did/did not [X] observe the plugging.

David K. Wann
David K. Wann P.I.R.T. II
(agent)

INVOICED

DATE 12-4-91

INV. NO. 33923

Phil S.