

4-070088

3-3

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-065-22,790 ⁰⁰⁻⁰⁰
220'S. & 220'W. of
SW NW /4 SEC. 10, 07 S, 23 W
3080 feet from S section line
4840 feet from E section line

Operator license# 4941

Lease: Fountain Well # 1

Operator: Union Valley Petroleum Corp.

County: Graham ^{126.75}

Address: R.R.4 - Box 120-Y
Enid, OK 73701

Well total depth 3900 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 211 feet

ABAND. oil well, Gas well, Input well, SWD., D&A X

Plugging contractor: Discovery Drilling License# 31548

Address: P.O. Box 763 - Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 3 Month: March Year: 1998

Plugging proposal received from: Tom Alm

Company: Discovery Drilling Phone: 785-623-2920

Were: Ordered 200 sxs 60/40 pozmix - 6% gel - 1/4# floseal per sack - one 8 5/8 W.P.
Spot plug through drill pipe with heavy drilling mud between all plugs.
8 5/8" set at 211.38'.

Plugging Proposal Received by: Rich Williams

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 8:00 A.M., Day: 3, Month: March, Year: 1998

Actual plugging report: No ar buckle cut.

1st. Plug at 2115' w/25 sxs. - Anhydrite 2103' - 2138'.

2nd. Plug at 1300' w/100 sxs. - Dakota Base 996' - 1300'.

3rd. Plug at 261' w/40 sxs. - Surface pipe at 211.38' + 50'.

4th. Plug at 40' w/10 sxs with 8 5/8" wiper plug.

15 sxs in rathole.

10 sxs in mousehole.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING. Elevation: 2396 GL

I did [] / did not [X] observe the plugging.

Richard Williams
(agent)

Form CP-2/3

INVOICED

DATE MAR 13 1998

INV. NO. 50056

3-3

3-12-98