

4-050254

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-065-22,778 -00-00

11-5

NE NW SE /4 SEC. 10 , 07 S, 23 W
2310 feet from S section line
~~1730~~ 1630 feet from E section line

Operator license# 5399

Lease: Trexler Well # A-1

Operator: American Energies Corporation

County: Graham 125.12

Address: 155 N. Market - Suite #710
Wichita, Kansas 67202
316-263-5785

Well total depth 3850 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 205 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Allied Cementing License# -

Address:

Company to plug at: Hour: A.M. Day: 5 Month: November Year: 1996

Plugging proposal received from: Tom Alm

Company: Phone:

Were: Order 200 sxs 60/40 pozmix - 6% gel - 1/4# Flo-seal per sack.
Anhydrite 2034' - 2069'.

3
10
11-12-96

Plugging Proposal Received by: Marvin Miller

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour 11:00A.M. , Day: 5 , Month: November , Year: 1996

Actual plugging report:

- 1st. Plug at 2050' with 25 sxs cement.
- 2nd. Plug at 1240' with 100 sxs cement.
- 3rd. Plug at 255' with 40 sxs cement.
- 4th. Plug at 40' with 10 sxs cement - 8 5/8" wiper plug.
- 15 sxs cement in rathole.
- 10 sxs cement in mousehole.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: 2340 GL

I did[] / did not[X] observe the plugging

Marvin Miller (agent)

Form CP-2/3

INVOICED
NOV 13 1996
46943