

To: **6 070896**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

206 *RP*

API NUMBER 15- 065-22,619-00-00R
NE NE NE SEC. 9, T 7 S, R 23 W/E
4950 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5011

Lease Name Seeger Well # 1-9

Operator: Viking Resources Inc.
Name & Address 105 S. Broadway #1040
Wichita, Kansas 67202
James B. Devlin

County Graham 126.75
Well Total Depth 3900 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 207

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A xx

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling License Number 5422
Address Wichita, Ks.

Company to plug at: Hour: _____ AM Day: 17 Month: Jan Year: 19 91

Plugging proposal received from Harold Maley
(company name) Abercrombie Drilling (phone) _____

were: 8 5/8 207 ft. s.p. cwc w/160 sks 60/40 poz 3% cc 2% gel. by Allied Cement.

K.C. well, elev. 2409 anhy 2099; no circ problems; mud 45 vis 9.5 weight. 8 w.l.

proposal 190 sks 60/40 poz 6% gel 3% ca cl and 1 sk f.c. Spot with drill stem; circ heavy mud between all plugs. 25 sks at 2100 ft.; 100 sks at 1300 ft. 40 sks at 250'.

10 sks at 40'; 15 sks rathole (circ) .

Plugging Proposal Received by Marion J. Schmidt
(TECHNICIAN) *MJS*
xx

Plugging Operations attended by Agent?: All _____ Part _____ None _____

Operations Completed: Hour: 6:00AM Day: 17 Month: Jan Year: 19 91

ACTUAL PLUGGING REPORT Viking ordered 190 sks 60/40 poz 6% gel 3% cc and 1 sk f.c.
Circ hole; Spotted w/drill stem, heavy mud between all plugs.

1. 1st plug at 2100 ft. w/25 sks.

2nd plug at 1300 ft. w/100 sks w/1 sk f.c.

3rd plug at 250 ft. w/40 sks cement.

4th plug at 40 ft. w/10 sks cement. 15 sks in rathole circ. Cemented by Allied Cement.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE FEB 14 1991
INV. NO. 30746

Signed Marion J. Schmidt
(TECHNICIAN)
Marion J. Schmidt