

To: 6 100378
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-30
API NUMBER 15- 065-22,507 - 00-00

N/2 SW SW, SEC. 32, T. 7 S, R. 24 W/E
990 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT
4964

Operator License # _____ Lease Name Goddard A. Well # 1

Operator: D C F Exploration County Graham 127.24

Name & Address: 940 Wadsworth Blvd. Well No. 3915 feet

Suite 100 Plug or Pipe: Size _____ feet

Lakewood, Co. 80215 Surface Casing: Size 8 5/8 feet 226

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ U&A x

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling Co. License Number 5302

Address Wichita, Ks. 67202

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Mike Wagner

(company name) Red Tiger (phone) _____

were: Spot through drill pipe w/heavy mud between all plugs.

1st plug at 2050' w/25 sks

2nd plug at 1200' w/100 sks

3rd plug at 270' w/40 sks

4th plug at 40' w/wiper plug and 10 sks

Rathole 15 sks Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None x

Operations Completed: Hour: 11:30PM Day: 30 Month: Jan Year: 19 89

ACTUAL PLUGGING REPORT Hole reported plugged as above

Order 190 sks 60/40 Poz w/6% Gel and 2 sks F.C.

Elevation: 2351' Anhydrite depth: 2044' - 71'

Remarks: Did not penetrate Arb. Cemented by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If applicable, do not) observe this plugging.

DATE 3-14-89

INV. NO. 24083

Handwritten initials

Signed [Signature]
D. K. Wann (TECHNICIAN)