

6 031137

7-8

API NUMBER 15-065-02960-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION SE SE SE, SEC. 32, T 7 S, R 24 W/EX  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

330 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Nana NW Well # Unit 101

Operator: Oxy USA Inc.

County Graham 127.40

Name & Address 3545 NW 58th St.  
Oklahoma City, Ok

Well Total Depth 3920 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 227

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement Co. License Number

Address Russell, Ks.

Company to plug at: Hour: PM Day: 8 Month: July Year: 19 88

Plugging proposal received from Pringle

(company name) Oxy USA (phone)

were: 8 5/8" set at 227' w/150 sks cwc. 5 1/2" set at 3920' w/125 sks.

PBTD 3886'. Perfs 3749' - 3862'. Shots at 2050' Anhy 1200' below Dakota. Order

300 sks Cement Blend w/100# Celloflake 1 sk 600# Hulls. Allied Cement Co. Wellbrock

Hensley Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12:00PM Day: 8 Month: July Year: 19 88

ACTUAL PLUGGING REPORT Squeezed 8 5/8" w/270 sks Cement Blend w/500# Hulls

mixed in last 150 sks to max Psi 400#. Close in 200#. Squeezed 8 5/8 w/50 sks Cement

Blend w/100# Hulls to max Psi 750#. Close in Psi 200#. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-20-88

Signed Carl Goodrow (TECHNICIAN)  
Carl Goodrow

INV. NO. 22312