

6 030781

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-065-21049-00-00

C/1/2 SW 5/4 SEC. 32, T. 7 S, R. 24 WE

660 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5134

Lease Name GODDARD Well # 1-32

Operator: GRAHAM-MICHAELIS CORP.

County GRAHAM 127.14

Name & Address P.O. Box 247

Well Total Depth 3912' feet

WICHITA, KANSAS

Conductor Pipe: Size \_\_\_\_\_ feet

67201

Surface Casing: Size 8 5/8" feet 312'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor KELSO CASING PULLING License Number 6050

Address CHASE, KANSAS

Company to plug at: Hour: PM Day: 15 Month: 8 Year: 19 86

Plugging proposal received from RON HOOVER

(company name) KELSO CASING (phone) \_\_\_\_\_

were: 8 5/8" SET @ 312' w/ 180 SX. 4 1/2" SET @ 3911' w/ 150 SX. PERF. 3740'-42'  
ORDER SAND & COM. CNT. SHOOT & PULL PIPE ORDER 200 SX. ATL  
EMT. MIX. 5 SX. HULLS ALLIED CNT. CO. OWS WATER TRUCK & SAABE  
WATER TRUCK.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:50 PM Day: 15 Month: 8 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND TO 3690' SPOT 4 SX. COM. CNT. ON  
SAND w/BAILER. SHOT 5 TIMES @ 1830'-1630'-1440'-1025'-834'  
RECOVERED 834' OF 4 1/2" CASING.

TIE ON TO 8 5/8" CASING MIX. & Pump 5 SX. HULLS WITH 200 SX.  
ATL CNT. MIX. MAX. PSI 500# CLOSE IN 200# CHECKED ON  
B-19-86 CEMENT @ 1' BELOW BASE OF CELLAR. IN 8 5/8"

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE SEP 3 1986

INV. NO. 14861

PLUGGED

SEP 2, 1986  
SEP 2 1986

Signed Carl Goodrow  
(TECHNICIAN)

8.29-86