

225 R

4-050142

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-065-22,688-00-00

NW SE SE /4 SEC. 09, 07 S, 23 W  
990 feet from S section line  
990 feet from E section line

Operator license #30606 Lease Brant well #1-9

Operator: Murfin Drilling Co. Inc. County Graham

Address: 250 N. Water Suite 300 Well total depth 3970 feet <sup>129.02</sup>  
Wichita, Kansas 67202 Conductor Pipe:        inch @        feet  
(316)267-3241 Surface pipe 8 5/8 inch @ 267 feet

Aband. oil well       , Gas well       , Input well       , SWD       , D & A X

Plugging contractor: Murfin Drilling Co. Inc. License#       

Address:       

Company to plug at: Hour: PM Day: 23 Month: August Year: 1992

Plugging proposal received from: Rodney Farr

Company: Murfin Drilling Co. Inc. phone:       

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2160 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1340 feet " 100 " Mousehole: 10 sacks

3rd plug @ 315 feet " 40 "

4th plug @ 40 feet " 10 " with 8 5/8" wiper plug

Plugging Proposal Received by: Marvin L. Miller

Plugging operations attended by agent? All[        ], Part[        ], None[ X ]

Completed: Hour: 12:30PM, Day: 23, Month: August, Year: 1992

Actual plugging report: Hole reported plugged as above.

Order 200 sx 60/40 pozmix w/ 6% gel and 1/4# celloflake or flowcel per sk

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: Elevation: 2442, Anhydrite: 2141-2174 feet, Anhydrite plug 2160  
Bottom plug (in place): Yes X, Calc       , No        Arbuckle: None <sup>9-4-92</sup>

Did NOT penetrate Arbuckle, cemented by Allied Cementing Company CONSERVATION DIVISION  
Wichita, Kansas

I did not [ X ] observe the plugging. Marvin L. Miller

DATE 9-24-92

INV. NO. 36249

Marvin L. Miller P.I.R.T.II  
(agent)