

15-065-02968-00-01

5-12

NO C

86

6 031253

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1957 E9707

NE SE NE, SEC. 28, T 7 S, R 25 W/E

3630 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Blazier Unit Well # 304 W

Operator: Oxy USA Inc.

County Graham 126.30

Name & Address

Well Total Depth 3886 feet

Box 38

Conductor Pipe: Size feet

Hill City, Kansas 67642

Surface Casing: Size 8 5/8 feet 238

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number

Address Oberlin, Kansas

Company to plug at: Hour: AM Day: 12 Month: May Year: 19 89

Plugging proposal received from Pringle

(company name) Oxy USA (phone)

were: 8 5/8" set at 238' w/225 sks cwc. 5 1/2" set at 3885' w/175 sks PBSD 3768'.

Perf 3700' - 21'. D.V. tool at 2165' cwc w/475 sks. Order 50 sks common cement 300 sks 65/35 poz 105 gel 500# hulls. Halliburton Cement Co. Wellbrock water. Murfin ran tubing.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:30AM Day: 12 Month: May Year: 19 89

ACTUAL PLUGGING REPORT Squeezed 5 1/2" casing w/50 sks common cement followed

w/260 sks cement blend w/500# hulls mixed into max psi 400# close in 400#. Plug complete.

Loaded hole through tubing.

RECEIVED STATE CORPORATION COMMISSION

JUN 26 1989 JUN 26 1989

CONSERVATION DIVISION Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed Carl Goodrow (TECHNICIAN) Carl Goodrow

INVOICED

DATE 6-27-89

INV. NO. 25133