

6070209

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-22, 026-00-00

SE-NE-NE, SEC. 31, T. 7 S, R. 25 W

4290 feet from N(S) section line

330 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6031

Lease Name BEST Well # 2

Operator: STAAB OIL Co.

County GRAHAM

Name & Address H.C. 39 BOX 114

Well Total Depth 3940 128.95 feet

HAYS, KANSAS.

Conductor Pipe: Size 0 feet

67601

Surface Casing: Size 8 5/8 feet 254

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated TAG #269

Plugging Contractor HELBERG OIL Co License Number 5669

Address MORLAND, KANSAS.

Company to plug at: Hour: 4:00 PM Day: 2 ND Month: AUG Year: 19 84

Plugging proposal received from CHARLIE MC DONALD.

(company name) STAAB OIL COMPANY. (phone) 913-625-5013

were: 8 5/8" - 254 FT 50. CUL. 1 1/35 SK COMMON GEL - CA-CL - BY SUN CMT.

Order 195 SK 50/50 Pozmix GEL - CA-CL - 1 SK 7/10 CUL. AND 8 5/8" PLUG.

SPOT WITH DRILL STEM - TURN HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS.

BASE KC WELL - NO CIRCULATION PROBLEMS, ELV 2484, ANH 2152

Plugging Proposal Received by [Signature] (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:15 PM Day: 2 ND Month: AUG Year: 19 84

ACTUAL PLUGGING REPORT

ORDERED 195 SK 50/50 Pozmix GEL - CA-CL - 1 CELE - AND 8 5/8" PLUG

SPOTTED WITH DRILL STEM - TURNED HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS

1st PLUG @ 2160 FT 1/25 SK CNT, 2nd PLUG @ 1170 1/100 CNT 1 SK 7/10 CELE.

3rd PLUG @ 270 FT 1/50 SK CNT, 4th PLUG SOLID BRIDGE @

40 FT @ 0 1/10 SK CNT, 10 SK (Rat hole Circulat.)

Remarks: CEMENTED BY SUN CMT

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-17-84

INV. NO. 3233

RECEIVED STATE CORPORATION COMMISSION AUG 13 1984 AUG 13 1984 CONSERVATION DIVISION Wichita, Kansas

Signed [Signature] (TECHNICIAN) 8-10-84 19 FORM CP-2/3 Rev. 01-84