

4-031904

1-31

15-065-30175-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 1966

C SW NE /4 SEC. 36, 07 S, 25 W
3300 feet from S section line
1980 feet from E section line

Operator license# 6009 Lease Moore well # A-1

Operator: Double Eagle Exploration, Inc. County Graham 129.68

Address: 800 West 47th Street Well total depth 3990 feet
Suite 318 Conductor Pipe: 0 inch @ 0 feet
Kansas City, MO 64112 Surface pipe 8 5/8 Inch @ 216 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 31 Month: January Year: 94

Plugging proposal received from: Pat Walters

Company: Double Eagle Exploration, Inc. Phone: _____

Were: Order 325 sxs. 60/40 pozmix - 10% gel - 500# hulls.
Critical control areas are 2180' Anhy. and Kiowa SH 975'.

RECEIVED
FEB 9 1994
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 3:30P.M., Day: 31, Month: January, Year: 94

Actual plugging report: 8 5/8" set @ 216' w/200 sxs. cwc. 4 1/2" set @ 3988' w/125 sxs. P.B.T.D. 3988'. Prod. Perf. 3926' - 3929'. Critical area control shots @ 2180' and 975'. Squeezed 8 5/8" with 100 sxs. cement blend with 100# hulls to Max. P.S.I. 300#. Close in P.S.I. 300#. Squeezed 4 1/2" with 225 sxs. cement blend with 400# hulls mixed in to Max. P.S.I. 1300#. Close in P.S.I. 400#. Plug complete.

Remarks: _____
Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: _____ GL

I did / did not observe the plugging. Carl Goodrow

INVOICED

DATE 2-9-94

INV. NO. 39907

(agent)
Form CP-2/3

1-31 MAR 30 1994