

4-031905

1-31

15-065-20065-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: ~~15-065-30312-00-00~~

C E2 NW /4 SEC. 36, 07 S, 25 W
3960 feet from S section line
3300 feet from E section line

Operator license# 6009 Lease Moore well # 2

Operator: Double Eagle Exploration, Inc. County Graham

Address: 800 West 47th Street Well total depth 3960 feet 128.70
Suite 318 Conductor Pipe: 0 inch @ 0 feet
Kansas City, MO 64112 Surface pipe 8 5/8 Inch @ 206 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 31 Month: January Year: 94

Plugging proposal received from: Pat Walters

Company: Double Eagle Exploration, Inc. Phone: _____

Were: Order 200 sxs. 60/40 pozmix - 10% gel - 500# hulls.

RECEIVED
STATE CORPORATION COMMISSION

FEB 9 1994
Feb 9, 1994
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 12:30P.M., Day: 31, Month: January, Year: 94

Actual plugging report: 8 5/8" set @ 206' w/150 sxs. cwc. 4 1/2" set @ 3957' w/175 sxs. D.V. tool set @ 2164' w/600 sxs. cwc. P.B.T.D. 3957'. Prod. Perf. 3851' - 3854'. Squeezed 4 1/2" with 185 sxs. with 500# hulls mixed in to Max. P.S.I. 1200#. Close in P.S.I. 800#. Cement at surface in braden head. Plug complete.

Remarks: _____
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: _____ GL

I did observe the plugging. Carl Goodrow

INVOICED
DATE 2-9-94
INV. NO. 39909
1-31 MAR 30 1994

(agent)
Form CP-2/3