

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22684-00-061
Spot: CE2NE Sec/Twnshp/Rge: 6-7S-23W
3960 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: PARKER B Well Number: 2
County: GRAHAM Total Vertical Depth: 3950 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER. STE 300
WICHITA, KS 67202

Conductor Pipe: Size feet: 8/28.38
Surface Casing: Size 8.625 feet: 301 185 SX CMT
Production: Size 4.5 feet: 2175 450 SX CMT
Liner: Size feet:

Well Type: SWD UIC Docket No: D26567.0 Date/Time to Plug: 06/07/2002 2:00 PM

Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Ordered 175 sxs 60/40 pozmix - 500# hulls.
Plugging Perfs and bridge plug set: 1872' - 1910'.
Method: PBTB 2154'.
Junk in hole at 480'.

Plugging Proposal Received By: PAT STAAB

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 06/07/2002 2:30 PM

KCC Agent: PAT STAAB

Actual Plugging Report:

Allied Cementing tied onto casing and pumped 25 sxs 60/40 pozmix, followed by 110 sxs with 500# hulls mixed in.
Max. P.S.I. 600#. S.I.P. 500#.
Tied onto backside and pumped 15 sxs 60/40 pozmix with Max. P.S.I. 300#. S.I.P. 150#.
Job completed.

RECEIVED

JUN 19 2002

KCC WICHITA

6-19-2002

Remarks: ALLIED CEMENTING COMPANY - TICKET #6476.

Plugged through: CSG

District: 04

Signed Pat Staab

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 6-24-02

INV. NO. 2002061990

JUN 17 2002