

5-27

4-031823

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-065-22,713 -00.00

NW NW NW /4 SEC. 05, 07 S, 23 W  
4950 feet from S section line  
4950 feet from E section line

Operator license# 4767 Lease Anna White well # 1

Operator: Ritchie Exploration, Inc. County Graham

Address: 125 N. Market Well total depth 3950 feet <sup>128.37</sup>  
Suite 1000 Conductor Pipe: 0 inch @ 0 feet  
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 298 feet

Aband. oil well     , Gas well     , Input well     , SWD     , D & A X

Plugging contractor: Murfin Drilling License# 30606

Address: Wichita, Kansas 67202

Company to plug at: Hour: A.M. Day: 27 Month: May Year: 93

Plugging proposal received from: Lloyd Dellett

Company: Murfin Drilling, Inc. Phone:                     

Were: Order 190 sxs. 60/40 pozmix - 6% gel. - 3% c.c.  
Condition hole with heavy mud.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[      ], Part[      ], None[ X ]

Completed: Hour: 2:45A.M., Day: 27, Month: May, Year: 93

Actual plugging report: Spot cement plugs with drill pipe.

1st. plug @ 2200' w/25 sx.

2nd. plug @ 1340' w/100 sx.

3rd. plug @ 350' w/40 sx.

4th. plug @ 40' w/10 sx. with W.P.

Circulate 15 sx. in rathole.

Remarks: Anhy. 2180' - 2212'.

Condition of casing(in hole): GOOD      BAD      Anhy. plug: YES      NO     

Bottom plug(in place): YES     , CALC     , NO      Dakota plug: YES      NO     

Plugged through TUBING     , CASING     . Elevation: 2487

I did not observe the plugging. Carl Goodrow

DATE 6-17-93

REV. NO. 37943

5-27

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 17 1993  
CONSERVATION DIVISION  
Wichita, Kansas  
DH (agent)  
Form CP-2/3 6-17-93