

1-31 15-065-20118-00-01

4-031906

E-24,955

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-

C NW NE /4 SEC. 36, 07 S, 25 W
4620 feet from S section line
1980 feet from E section line

Operator license# 6009 Lease Moore well # 3SWD

Operator: Double Eagle Exploration, Inc. County Graham

Address: 800 West 47th Street Well total depth 4053 feet ^{131.72}
Suite 318 Conductor Pipe: 0 inch @ 0 feet
Kansas City, MO 64112 Surface pipe 8 5/8 Inch @ 219 feet

Aband. oil well , Gas well , Input well , SWD X, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 31 Month: January Year: 94

Plugging proposal received from: Pat Walters

Company: Double Eagle Exploration, Inc. Phone:

Were: Order 250 sxs. 60/40 pozmix - 10% gel - 500# hulls.

RECEIVED
STATE CORPORATION COMMISSION

FEB - 9 1994

Feb 9, 1994
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 10:30A.M., Day: 31, Month: January, Year: 94

Actual plugging report: 8 5/8" set @ 219' w/250 sxs. cwc. 4 1/2" set @ 4049' w/150 sxs. D.V. tool set @ 2190' w/500 sxs. cwc. P.B.T.D. 4049'. Prod. Perf. 3941' - 3966'. Squeezed 4 1/2" with 235 sxs. with 500# hulls mixed in to Max. P.S.I. 900#. Close in P.S.I. 600#. Tested and squeezed 8 5/8" with 15 sxs. to Max. P.S.I. 500#. Close in P.S.I. 500#. Plug complete.

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did not [] observe the plugging. Carl Goodrow

DATE 2-9-94

HO

(agent)

Form CP-2/3

INV. NO. 39908

7-31 MAR 30 1994