

6 090201

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-179-20,762-00-00
SE 1/4, SEC. 19, T. 7 S, R. 30 W 1/4
1980 feet from NIS section line
1650 feet from NIE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9123

Lease Name Eldon A. Teal Well # 1-19
County Abilene 139.75

Operator: Diamond Shamrock Exploration
Name & Address Company
P.O. Box 631
Amarillo, Texas 79173

Well Total Depth 4300 feet
Conductor Pipe: Size - feet -
Surface Casing: Size 8 5/8 feet 331

Abandoned Oil Well - Gas Well - Input Well - SWD Well - D&A

Other well as hereinafter indicated -

Plugging Contractor Lawson Drilling Co., Inc. License Number 5657
Address Wichita, Kan. 67202

Company to plug at: Hour: - Day: 31 Month: December Year: 19 84

Plugging proposal received from Bob Felder
(company name) Lawson Drilling Co., Inc. (phone) 316-263-3201

were: Order 180 sks. 50/50 porous, 6 7/8 gel, 3 7/8
Cal. C. & 8 5/8" sweep plug, spot all plugs
through drill pipe w/ heavy mud between all
plugs.

Plugging Proposal Received by Edwin A. Schumacher
(TECHNICIAN)

Plugging Operations attended by Agent?: All - Part - None

Operations Completed: Hour: 1:00 P.M. Day: 31 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 1st plug 2625' w/ 20 sks.
2nd plug 1985' w/ 100 sks. & 1 sk. Cells-Flake
3rd plug 380' w/ 40 sks.
4th plug 40' solid bridge 1 sk. hulls & 10 sks.
10 sks. in rat hole

Remarks: Elevation - 2958', Anhydrit - 2620', Carbuck - 20
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 1-16-85
INV. NO. 6508
1-31

Signed Edwin A. Schumacher
(TECHNICIAN)
RECEIVED STATE CORPORATION COMMISSION
JAN 17 1985
01-07-1985
CONSERVATION DIVISION
Wichita, Kansas
FORM CP-2/3
Rev. 01-84

FEB 27 1985
MAR 22 1985
MAY 02 1985
(SUSAN)

15