

To: 6 031550  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

6-18 1942  
API NUMBER 15- 193-20,123-00-00  
C SW SW, SEC. 13, T 7 S, R 31 (W) ■  
660 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5652  
Operator: Mustang Companies, Inc.  
Name & Address: P.O. Box 1609  
Great Bend, Kansas 67530

Lease Name Seifert Well # 3  
County Thomas 139.75  
Well Total Depth 4300 feet  
Conductor Pipe: Size - feet -  
Surface Casing: Size 8 5/8 feet 300'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A   
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton Services License Number -  
Address Oberlin, Kansas

Company to plug at: Hour: P.M. Day: 18 Month: 6 Year: 19 91

Plugging proposal received from Rayford Clark  
(company name) Mustang (phone) \_\_\_\_\_

were: 8 5/8 set @ 300' w/220 4 1/2 set @ 4289' w/125 sxs. Perf. 4180'-85'.  
Order 300 sxs. 65/35 poz. 10% gel. 600# Hulls. Halliburton Services  
LaRue Water Trucks. Hole open across perms. Rig had tools to bottom  
in checking out well. Shots @ 1750 and 2200.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5:00 P.M. Day: 18 Month: 6 Year: 19 91

ACTUAL PLUGGING REPORT Squeezed 4 1/2 w/200 sxs. cement blend w/500# Hulls.

Mixed in to Max. P.S.I. 600#. Close in P.S.I. 400#. Squeezed 8 5/8 w/100 sxs.  
cement blend w/100# hulls mixed in to. Max. P.S.I. 300#. Close in P.S.I. 300#.

Plug Complete.  
RECEIVED  
STATE CORPORATION COMMISSION  
07-22-1991  
JUL 22 1991

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED  
I (and ~~you~~) observe this plugging.

DATE 8-6-91  
INV. NO. 32572

Signed Carl Goodrow  
(TECHNICIAN)