

6 070572

7-3-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 179-20,895-00-00

SW SW NE, SEC. 1, T 7 S, R 26 W/E
2970 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5474

Lease Name Scott Well # 1

Operator: Northern Lights Oil Co.
Name & Address: 212 North Market #400
Wichita, Kansas 67202

County Sheridan 126.75
Well Total Depth 3900 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 346

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Mallard Drilling Inc. License Number 4958

Address 405 Centry Plaza Wichita, Kansas 67202

Company to plug at: Hour: 8:30 PM Day: 3 Month: July Year: 19 87

Plugging proposal received from Jay Schneider

(company name) Mallard Drilling Co. Inc. (phone) 316-263-8218

were: 8 5/8" - 346ft. SP. CWC w/175 sks 60/40 - 2-3 by Allied Cmt.

Proposal - 210 sks 60/40 Pozmix 6% Gel 2% CaCl. 1 sk Flocele, and 8 5/8" plug.

Spot with drill stem; Recondition hole; Mud between all plugs.

Elv. 2579', Anh 2185'; No circulation problems. Mud 40 Vis - 9.2 weight and

9.6 water loss. 25 sks at 2175' - 100 sks cement at 1425' - 50 sks at 390' - 10 sks
and 1 sk Flocele mixed in

Hulls plug at 40'. Plugging Proposal Received by Marion J. Schmidt
(TECHNICIAN)

15 sks rat hole. 10 sks mouse hole. (circulate)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 8:30 PM Day: 3 Month: July Year: 19 87

ACTUAL PLUGGING REPORT Ordered 210 sks 60/40 Pozmix 6% Gel 3% CaCl.

1st Flocele and 8 5/8" plug.

Spotted with drill stem; reconditioned hole; mud between all plugs.

1st plug at 2175 w/25 sks. 2nd plug at 1425 w/100 sks and 1 sk Flocele

3rd plug at 390 w/50 sks. 4th plug Hulls plug at 40 w/10 sks cmt.

15 sks rat hole (circulate) 10 sks mouse hole. (Circulate)

Remarks: 7-14-87 Cemented by Allied Cementing.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-10-87

INV. NO. 17781

7-3

Signed Marion J. Schmidt
Marion J. Schmidt (TECHNICIAN)

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
AUG - 8-27-87