

6 090337

7-6-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 179-20,898-00-00
SE, SEC. 29, T 7 S, R 29 (W/X)

TECHNICIAN'S PLUGGING REPORT

Operator License # 8000

1980 feet from S section line
1980 feet from E section line

Operator: Pan Canadian Petroleum Co.
Name & Address: P. O. Box 929
Denver, Colorado 80203

Lease Name Pope 33-29 Well # 2
County Sheridan 138.78

Well Total Depth 4270 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 315

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling Inc. License Number 5422

Address Wichita, Kansas

Company to plug at: Hour: Day: 6 Month: July Year: 19 87

Plugging proposal received from Harold Maley

(company name) Abercrombie Drilling Inc. (phone)

were: Order 185 sks 60/40 Pozmix 6% Gel and 8 5/8" wiper plug.

Spot all plugs through drill pipe with heavy mud between all plugs.

Plugging Proposal Received by Edwin A. Schumacher
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:30 AM Day: 6 Month: July Year: 19 87

ACTUAL PLUGGING REPORT 1st plug 2540' w/20 sks

2nd plug 1680' w/100 sks

3rd plug 365' w/40 sks

4th plug 40' wiper plug and 10 sks

15 sks rat hole.

RECEIVED
STATE CORPORATION COMMISSION
09-25-1987
SEP 25 1987
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Elevation 2856' Anhydrite 2532' Arbuckle No B. J. Titan

(If additional description is necessary, use BACK of this form.)

INVOICED

(do not) observe this plugging.

DATE 9-29-87

Signed Edwin A. Schumacher
Edwin A. Schumacher (AN)

INV. NO. 18304 OCT 29 1987 DEC 03 1987