

4-1 4-032221

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-179-20,597-00-00

C SW NW /4 SEC. 19, 7, 30W
3300 feet from S section line
4620 feet from E section line

Operator license# 31668 Lease: Gilchrist Well # 19-5

Operator: H & H Investments County: Sheridan 151.52

Address: 3705 J.P. Drive Well total depth 4662 feet
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 324 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 1 Month: April Year: 1997

Plugging proposal received from: Ron

Company: H & H Investments Phone: -

Were: Order 120 sxs 60/40 pozmix - 10% gel - 300# hulls - 13 sxs gel.

04-07-1997

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 12:15 P.M., Day: 1 Month: April Year: 1997

Actual plugging report: 8 5/8" set at 324' w/270 sxs. cwc. 4 1/2" set at 4270' w/150 sxs.
Prod. Perfs 3696' - 3698' - 4121' - 4125'.

Squeezed 4 1/2" w/20 sxs cement blend w/300# hulls mixed in, followed by 13 sxs gel, followed by 100 sxs cement blend to Max. P.S.I. 300#. Held. Test backside to 300'. Would not take. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING. Elevation: GL

I did [X] / did not [] observe the plugging.

Carl Goodrow (agent)

INVOICED
DATE 4-17-97
INV. NO. 47969