

15-065-01308-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 21 1969
CONSERVATION DIVISION
Wichita, Kansas

4/21/69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Specter Pipe and Supply, Incorporated.

Complete Address Box #169, Russell, Kansas.

Lease Name Wanker Well No. 1

Location SE 1/4 SW-NE Sec. 35 Twp. 7 Rge. (E) (W) 23

County Graham Total Depth 3765'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Lynch Casing Pulling Company.

Address Rte #4, Great Bend, Kansas. License No. 457

Operation Completed: Hour 5:45 PM Day 16 Month 4 Year 1969

The above well was plugged as follows:

230'--8 5/8" Surface casing, cement circulated with 175 Sx.
3765'--5 1/2" Production casing cemented on bottom with 125 Sx. No Plug back nor perforations indicated.

Pushed plug to 3500', built sand bridge from 3500' to 3475' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing and squeezed well initially with 5 sacks hulls and 10 sacks gel and followed with 100 Sx. cement from 1200' to 875' then 16 sacks gel from 875' to 250' and followed with 20 Sx. cement from 250' to 190' then 4 sacks gel from 190' to 30' and finally 10 Sx. cement from 30' to bottom of cellar. Maximum pump-in pressure-150#. Final shut-in pressure-50#. (Mudding & cementing by Allied).

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/21/69
INV. NO. 9625-4

Signed: M. L. Nichols
Well Plugging Supervisor