

15-065-20650-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 7 1974
2-7-1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name National Oil Company.

Complete Address 200 West Douglas, Wichita, Kansas.

Lease Name Hedge Well No. 1

Location SW-SW-SE Sec. 36 Twp. 7 Rge. (E) (W) 23

County Graham Total Depth 3745'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor John O. Farmer, Incorporated.

Address 370 W. Wichita, Russell, Kansas. License No.

Operation Completed: Hour 9:00 PM Day 4 Month 2 Year 1974

The above well was plugged as follows:

202'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 750'.

Circulated hole with heavy mud. Pulled DP to 975' and displaced 110 Cu. Ft. cement
thru DP from 975' to 650'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru DP
from 215' to 140'. Pulled DP, set bridge @ 140' with 1/2 sack hulls and 10 Cu. Ft. cement
to bottom of cellar.

INVOICED I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Dickel
Well Plugging Supervisor

DATE 2/8/74
NO. 8548-W