

15-065-30135-00-00

Form CP-3
Rev. 6-26-62

R

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

2/12/65

FEB 12 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Chief Drilling Company, Incorporated,

Complete Address: Box # 797, Great Bend, Kansas.

Lease Name Dawson Well No. 1

Location CSE-NE Sec. 34 Twp. 7 Rge. (E) (W) 23

County Graham Total Depth 2655

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: THIS WELL WAS DRILLED TO THE FORT RILEY,
NO SURFACE PIPE WAS SET.

Plugging Contractor: Above

Address: _____ License No. _____

Operation Completed: Hour 8:15AM Day 8 Month 2 Year 1965

The Above well was plugged as follows:

Hole was left full of heavy drilling mud, Ran drill pipe to 540' and
displaced 20 Sx. cement thru drill pipe. Pulled drill pipe, set plug @
155' and displaced 60 Sx. cement thru Drill pipe. Ran float on
measuring line and found top of plug @ 40'. Set Bridge and filled hole
to bottom of cellar with 15 sx. cement.

(Cementing operations performed by Sun Oil Well Cementing, Inc.,)

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2-12-65

INV. NO. 677-W

Signed: A. L. Nichols
Well Plugging Supervisor