

15-065-20292-00-00

Form CP-3
Rev. 6-4-68

KANSAS

JP
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 22 1969

CONSERVATION DIVISION
Wichita, Kansas

12/22/69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Landes Exploration Company,
Complete Address 416 Union Center Building, Wichita, Kansas.
Lease Name Kline Well No. 1
Location S/2-SE Sec. 34 Twp. 7 Rge. (E) (W) 23
County Graham Total Depth 3620'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor L. J. Dreiling & Sons, Incorporated,
Address R. R. #2, Victoria, Kansas. License No.
Operation Completed: Hour 4:00 PM Day 15 Month 12 Year 1969

The above well was plugged as follows:

202'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 850'.

Circulated hole with heavy mud. Pulled DP to 1075' and displaced 100 Sx. cement thru
DP from 1075' to 750'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from
215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 12/23/69
INV. NO. 1117-W