



KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Mack Oil Company,

Complete Address: 812 Union Center Building, Wichita, Kansas.

Lease Name Bair Well No. 1

Location CNW-SW Sec. 18 Twp. 7 Rge. (E) (W) 41

County Sherman Total Depth 5470'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Above

Address:      License No.     

Operation Completed: Hour 3:00 PM Day 12 Month 1 Year 1969

The Above well was plugged as follows:

384'--8 5/8" Surface casing, cement circulated with 300 Sx.  
Top of Dakota section @ 2495'.

Circulated hole with heavy mud. Pulled DP to 2725' and displaced 120 Sx. cement thru  
DP from 2725' to 2335'. Pulled DP to 425' and displaced 25 Sx. cement from 425' to  
350'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of  
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/16/69  
INV. NO. 9199-W

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 16 1969  
CONSERVATION DIVISION  
Wichita, Kansas

1/16/69

Signed: M. L. Pichok  
Well Plugging Supervisor