

15-163-20154-00-00 *SP*

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUN 7 1971
CONSERVATION DIVISION
Wichita, Kansas
6/7/71

Operator's Full Name Bob Chesney

Complete Address Woodston, Kansas 67675

Lease Name Kellog Well No. 1

Location SE NE SW Sec. 30 Twp. 8 Rge. (E) (W) 16

County Rooks Total Depth 3370'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Forbes Gasing Pulling

Address Box 221 Great Bend, Kansas License No. 637

Operation Completed: Hour 12:30 P Day 3 Month 6 Year 1971

The above well was plugged as follows:

Total Depth 3370' 8 5/8 csg set at 235' cwc 145 sk.

1/2 csg set at 3130' cw 75 sk cmt.

1/2 csg PB and perf. (3060)

Filled 1/2 csg W/sd to 3043 -Dumped 4 sk cmt w/dump bailer.

Recovered 715' of 1/2 csg.

Pumped down 8 5/8 csg W/20 sk gel W/3 sk hulls, 60 sk 60-40 poz 2% -7 sk gel -

release plug and pumped 60 sk 60-40 poz 2%.

I hereby certify that the above well was plugged as herein stated.

Signed: *Leo J. Massey*
Well Plugging Supervisor

INVOICED
DATE 6-7-71
INV. NO. 3810-W