

15-181-20011-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 11 1972  
CONSERVATION DIVISION  
Wichita, Kansas  
1/11/72

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name U. S. Signal Oil & Gas Company, 1971 Program.  
Complete Address 125 Central Building, Midland, ~~Kansas~~ <sup>TEXAS</sup>  
Lease Name Signal '71 Baird Well No. 1  
Location CNE-NW Sec. 4 Twp. 7 Rge. (E) (W) 37  
County Sherman Total Depth 5568'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Red Tiger Drilling Company,  
Address 1720 Wichita Plaza, Wichita, Kansas. License No.         
Operation Completed: Hour 8:30 AM Day 9 Month 1 Year 1972

The above well was plugged as follows:

445'--8 r/8" Surface casing, cement circulated with 300 Sx.  
Top of Dakota section @ 1918' .

Circulated hole with heavy mud. Pulled DP to 2175' and displaced 110 Cu. Ft. cement  
thru DP from 2175' to 1850'. Pulled DP to 465' and displaced 30 Cu. Ft. cement thru  
DP from 465' to 390'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. D. Nichols  
Well Plugging Supervisor

DATE 1-13-72

INV. NO. 4980-W