

15-181-20009-06-00

Form CP-3
Rev. 6-4-68

KANSAS

Handwritten initials

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 2 1969
CONSERVATION DIVISION
Wichita, Kansas

9/2/69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Donald C. Slawson

Complete Address 408 One Twenty Bldg., Wichita, Kansas

Lease Name Welfrun "B" Well No. 1

Location C NE NW Sec. 4 Twp. 7 Rge. (E) (W) 39

County Sherman Total Depth 3280'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Murfin Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour Day 31 Month 8 Year 1969

The above well was plugged as follows:

RTD 3280' 8 5/8 csg set at 357' cwe. Cmt. Mat. 50-50 pez cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 2280' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 330' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/3/69

INV. NO. 404-W

Signed: Leo F. Messing
Well Plugging Supervisor