

15-163-20144-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
NOV 6 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Tilco, Et al

Complete Address: 815 Wichita Plaza Wichita, Kansas

Lease Name Brown Well No. 1

Location SW SW SE Sec. 32 Twp. 8 Rge. 16 (E) (W) XX

County Rooks Total Depth 3330

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: Leben Drlg.

Address: Wichita, Kansas License No.

Operation Completed: Hour 4:15P Day 1 Month 11 Year 1968

The Above well was plugged as follows:

RTD 3330' 8 5/8 csg set at 209' cwc Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 540' and displaced 70 sc cmt.

thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cmt. to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 11/6/68
INV. NO. 8777-U