

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15- 163-21,383-00-00

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name DUPONT OIL

Complete Address 214 SOUTH ROCK ROAD, #105 WICHITA, KANS.

Lease Name HUNTER Well No. #1

Location C-W 1/2 - SW - SW Sec. 4 Twp. 8^S Rge. 17^W (East) (West)

County ROOKS Total Depth 3461 FT

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor CIRCLE-M-DRILLING, INC

Address P.O. BOX 128 OBERLIN, KANS License No. _____

Operation Completed: Hour: 3:30 PM Day: 10TH Month: AUG Year: 19 81

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

8 5/8" - 215 FT SD. CUG w/ 115 ST COMMON - 2% GEL - 3% CA-CL
ORDERED 130 ST 50/50 Foz MIX 4% GEL - 3% CA-CL. + 8 5/8" PLUG.
SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.
1 ST PLUG @ 1780 FT w/ 45 ST CNT.
2 ND PLUG @ 200 FT w/ 40 ST CNT.
3 RD PLUG - SOLID BRIDGE HALLS - PLUG @ 40 FT TO w/ 10 ST CNT.
5 ST IN RAT HOLE.

CEMENTED BY HALLIBURTON CNT

RECEIVED

STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

INVOICED

AUG 17 1981

Signed: Merion Schmidt
Conservation Division Agent

DATE 9-25-81

CONSERVATION DIVISION
Wichita, Kansas

8-17-81

INV. NO. 7529W