

V KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-00294-00-00

RECEIVED  
STATE CORPORATION COMMISSION

APR 10 1964  
4-10-64  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Okmar Oil Co  
Complete Address: 1130 Wichita Plaza Wichita, Kans  
Lease Name Eckert Well No. 1  
Location NW NW SE Sec. 5 Twp. 8 Rge. (E) (W) 17  
County Rooks Total Depth 3317'  
Abandoned Oil Well x Gas Well      Input Well      SWD Well      D & A       
Other well as hereafter indicated:       
Plugging Contractor: Southwest Casing Pulling Co  
Address: Great Bend, Kans License No. 399  
Operation Completed: Hour 12 Noon Day 8 Month 4 Year 64

The Above well, was plugged as follows:

8 5/8" 117' circulated with cement - 5 1/2" 3315' with 100 sax cement -  
5 1/2" eaten into at 692' - Dakota will flow.

Pumped 5 Sax Gel & 10 sax weight mud to kill Dakota flow - pulled 692'  
5 1/2" - pumped 10 more sax gel mud to pressure up hole - pumped wiper plug  
followed by 130 sax cement - squeezed.

Mudding and Cementing by Southwest Pump truck - 200# pump pressure on Comp.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 4/10/64

INV. NO. 8923-W