

40
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-00615-00-00

RECEIVED
STATE CORPORATION COMMISSION

JUL 25 1963

CONSERVATION DIVISION
Wichita, Kansas

7-25-63

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Okmar Oil Co

Complete Address: 1130 Wichita Plaza Wichita, Kansas

Lease Name Forrest Well No. 2

Location NE SW SW Sec. 5 Twp. 8 Rge. (E) (W) 17

County Rooks Total Depth 3290

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Southwest Casing Pulling

Address: Great Bend, Kansas License No. 399

Operation Completed: Hour 1PM Day 20 Month 7 Year 63

The Above well was plugged as follows:

8 5/8" 108' circulated with cement - 5 1/2" 3284' with 100 sax cement & squeezed at 680' with 200 sax cement. Lane Well plug at 3250' - no perforations above plug.

Pumped hole full heavy gel mud (12 sax Gel & 16 sax weight gel) pulled 520' 5 1/2" - pumped cementing plug to 425' followed by 130 sax cement - cement 425' to 0'.

Mudding and cementing by Southwest Company pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edon Letty
Well Plugging Supervisor

DATE 7/25/63
INV. NO. 4465-U