

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 24 1974

CONSERVATION DIVISION
Wichita, Kansas

5-24-74

15-163-20521-00-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name John O. Farmer

Complete Address Box 352, 370 W. Wichita Ave., Russell, Kansas

Lease Name Behrens Well No. 1

Location SE SW NE Sec. 2 Twp. 8 Rge. (E) (W) 17

County Rooks Total Depth 3315'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Teels

Address License No.

Operation Completed: Hour 7 A Day 22 Month 5 Year 1974

The above well was plugged as follows:

RTD 3315' 8 5/8 csg set at 201' cwc 160 sk. Cmt. Mat. 50-50 poz W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 550' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 185' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo A. Massey
Well Plugging Supervisor

DATE 5/30/74
INV. NO. 9194-W