

DISTRICT CONSERVATION AGENT'S REPORT

TO:

15-163-00112-00-00

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 112-41

LOCATION SW SW SW

SEC. 4 TWP. 8 RGE. 17W

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Hunter

Operator Clay Phillips Address 430 W 23rd Hutchinson, Kans

Field _____ County Rooks

Total Depth 3399 Feet.

Plugging Contractor Arnett Pipe Pulling

Plugging Contractor's License No. 265

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 190' circulated with cement - 5 1/2" at 3385' with
100 sax cement behind.

Filled with sand to 3350', set 4 sax cement with dump bailer, pulled
2070' 5 1/2" - pumped hole full mud (35 sax Gel), pumped cementing
plug to 190', followed by 60 sax cement - Cement 190' to 0'.

Mudding and cementing by Halliburton Co.

Edon Petty
District Conservation Agent

Date 12-11-56

PLUGGING
FILE SEC 4 T 8 R 17W
BOOK PAGE 112 LINE 41

CONSERVATION DIVISION

12-17-56