

DISTRICT CONSERVATION AGENT'S REPORT

15-163-00421-00-00

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 47-14  
LOCATION NE NE NW  
SEC. 4 TWP. 8 RGE. 17

Dry Hole \_\_\_\_\_ Abandoned Oil Well <sup>X</sup> \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Dancer

Operator Murfin Drg Co Address Wichita, Kans

Field \_\_\_\_\_ County Rooks

Total Depth 3392 Feet.

Plugging Contractor Miller Casing Pulling

Plugging Contractor's License No. 12

Address \_\_\_\_\_

(Describe briefly the manner in which the well was plugged)

8 5/8" at 130' circulated with cement - 5 1/2" at 3253' with  
120 sax cement behind - Baker plugs to 3180', perforated at  
3148'

Filled with chat to 3130', set 4 sax cement with dump bailer,  
pulled 1930' 5 1/2" - pumped hole full mud (35 sax Gel), pumped  
cementing plug to 165' followed by 50 sax cement - cement 165'  
to 0'.

Mudding and Cementing by Sun Cementing Co

Edward Kelly  
District Conservation Agent

Date 3-31-56

**PLUGGING**  
FILE SEC 4 T 8 R 17w  
BOOK PAGE 47 LINE 14

STATE OF KANSAS  
APR 2 1956  
CONSERVATION DIVISION  
Wichita, Kansas

4-2-56