


DISTRICT CONSERVATION AGENT'S REPORT



TO:

15-163-19108-00-00

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 105-21

LOCATION NE SE NW

SEC. 5 TWP. 8 RGE. 17

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. B-2 Lease Stamper

Operator Murfin Drg Co Address Wichita, Kans

Field _____ County Rooks


Total Depth 3296 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 123' circulated with cement - 5 1/2" at 3296' with
150 sax cement behind - Lane Wells plugs at 3127', perforations
at 3094', filled with chat to 3050', set 4 sax cement with
dump bailer - pulled 2500' 5 1/2" - Pumped hole full mud, 90 sax.
Pumped cementing plug to 225' followed by 65 sax cement
filling hole with cement from 225' to 0'. at 200# pressure.
Mudding and Cementing by Globe Cementing Co.

PLUGGING
FILE SEC 5 T 8 R 17W
BOOK PAGE 105 LINE 21

RECEIVED
STATE CORPORATION COMMISSION
JUN 22 1953
CONSERVATION DIVISION
Wichita, Kansas


District Conservation Agent
Date 6-17-53

6-22-53