

DISTRICT CONSERVATION AGENT'S REPORT

15-163-00096-00-00

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 121-19

LOCATION _____

SEC. 6 TWP. 8 RGE. 17-W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Stamper

Operator Standard Oil & Gas Co Address Goekam - Main - Box #35


Field _____ County Moore

Total Depth 3386 Feet.

(Describe briefly the manner in which the well was plugged)

New Rotary Drilled Hole - Plugged back to 3092ft with cement & tested. Perforated between 3058 & 3053ft. Put in Plug & Bridge at 3040ft & 10 sacks cement with Heavy Bailer. Shot off 5 1/2" casing at 2500ft & pulled about 500 ft. Surface Pipe left in hole 13 3/8 - 158ft cemented all around. 8 3/4" - 1258ft cemented all around. Hole filled with Mud to 1258ft. Plug & 10 sacks of cement - Plug & 10 sacks

cement at 160ft. Surface Plug 20ft below surface & 10 sacks cement. Heavy Mud between all Plugs. Frank Correll - Pipe Puller & Plugger



C. M. Stough
District Conservation Agent
Date 1-1-47
PLUGGING
FILE SEC 6 T 8 R 17W
BOOK PAGE 121 LINE 19

8-4-47