

DISTRICT CONSERVATION AGENT'S REPORT

Handwritten scribble

TO:

15-163-00962-00-00

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 71-3

LOCATION SE NE SW

SEC. 6 TWP. 8 RGE. 17

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease _____ Walter _____

Operator V. D. Sidey Oil Co Address Box 387 Russell, Kans

Field _____ County Rooks

Total Depth 3407 Feet.

Plugging Contractor Barnes & Sons

Plugging Contractor's License No. 9

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 100' circulated with cement - 5 1/2" at 3389' with

100 sax cement behind.

Filled with sand to 3380', set 4 sax cement with dump bailer,

pulled 2800' 5 1/2" - pumped hole full mud (35 sax Gel), pumped

cementing plug to 190' followed by 60 sax cement - Cement 190'

to 0'.

Mudding and cementing by Halliburton Co.

RECEIVED
STATE CORPORATION COMMISSION

JUL 20 1956

CONSERVATION DIVISION
Wichita, Kansas

Handwritten signature

District Conservation Agent

7-21-56

Date 7-20-56

PLUGGING
FILE SEC. 6 T. 8 R. 17w
BOOK PAGE 71 LINE 3