

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-01351-00-00

RECEIVED
STATE CORPORATION COMMISSION

JUL 11 1961

CONSERVATION DIVISION
Wichita, Kansas

7-11-61

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Rooks

Location: SE SE SE Sec. 6 Twp. 8 Rge. _____ (E) _____ (W) 17

Name of Field: _____ Total Depth: 3387

I have this date completed supervision of plugging of:

Lease Name: Brown ~~Beorn~~ Well No. 2

Operator's Full Name: Okmar Oil Co

Complete Address: 820 Union Natl Bk Wichita, Kansas

Plugging Contractor Glenn & Smith

Address: Ellinwood, Kansas License No. 396

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 10AM Day 5 Month 7 Year 61

The above well was plugged as follows:

8 5/8" 122' circulated with cement - 5 1/2" 3382' with 100 sax cement.

Set 5 sax cement on bottom with dump bailer, pulled approximately 750'

5 1/2" - pumped hole full heavy mud (35 sax Gel), pumped cementing

plug followed by 100 sax cement. Cement to bottom cellar.

Mudding and cementing by Sun Cementing Co 200# pump pressure

Signed: Edward Petty
Conservation Division Agent

Reviewed: Harold J. Morris
Field Supervisor

Remarks:

INVOICED
DATE 7/20/61
INV. NO. 3402-W