

DISTRICT CONSERVATION AGENT'S REPORT

TO:

15-163-02674-00-00

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 105-22
LOCATION SW NW NE
SEC. 5 TWP. 8 RGE. 17

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. D-1 Lease Stamper
Operator Murfin Drg Co Address Wichita, Kans
Field _____ County Rooks
Total Depth 3359 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at ~~1222~~ 122' circulated with cement - 5 1/2" at 3345'
with 50 sax cement behind.

Filled with chat to 3330', set 4 sax cement with dump bailer,
pulled 2500' 5 1/2" - pumped in 50 sax mud, filling hole, pumped
in cementing plug to 185', followed by 60 sax cement filling
hole from 185' to 0' with cement.

Cementing by Sun Cementing Co

PLUGGING
FILE SEC. 5 T. 8 R. 17
BOOK PAGE 105 LINE 22

RECEIVED
STATE CORPORATION COMMISSION
JUN 17 1953

CONSERVATION DIVISION
Wichita, Kansas

6-17-53

[Signature]
District Conservation Agent

Date 6-13-53